



B.P:15753 Yaoundé

REGISTRE DE COMMERCE: RC/YAE/2013/B/70

NUMERO CONTRIBUABLE: MO41300045489W

TELEPHONE: 672907152/243084082/243823551

COURRIEL: nkomaluth11@gmail.com/info@tactictechltd.com

OFFER OF SERVICES

We design and supply skid mounted or packaged equipment. Our scope of supply includes the responsibility for all stages of project execution including initial design, detailed design of process, mechanical, electrical, control and instrumentation, manufacturing, testing, site erection and commissioning service, Electrical heat tracing, and a supply of required spare parts.

We provides also drilling procurement services for the oil & gas industry

We are able to assist with site issues regarding reciprocating compressors from minor trouble shooting to major refurbishment.

We have experienced Ariel qualified commissioning and service engineers available, and have direct access to all the spares that your installation might require.

We will provide a full range of spares, responding rapidly to requests and can supply spare parts for third party packages (following a site survey), as well as our own designed packages. Recommended Spares Lists are provided with all equipment packages supplied.

Our experts provide a depth of experience in all aspects of onsite services including but not limited to the following:

- Unpacking and Inspection of Equipment**
- Installation Supervision**
- Pre-commissioning/Testing of installed plant**
- Commissioning & Start-Up assistance**
- Equipment Condition & Maintenance Surveys**
- Optimisation of Plant Efficiency**
- Overhaul & Repair**
- PLC Control Modifications**
- Operator Training**

**AXH cooler beam re-
placement**



**Gas exchanger insula-
tion repair**



Compression package inspection before grouting








**Supervisor and
the E&I after a
job picture**



REBUILT OF AN ARIEL jgk/4 RECIPROCATING COMPRESSOR









**Piston
Valve &
packing**



**Suction bottle
removal**



**Throw 3
cylinder
removal**



New cylinder to install



Crank end cylinder head



Packing installed



Piston Installed



Valves Installed



Throw 3
rebuild



Carry out trial alignment trial alignment

WAUKESHA

Carryout a Part internal,part external inspection the Waukesha gas engine, consisting of rocker cover removal, crankcase door removal, main bearing removal, con rod bearing removal, Boro scope cylinder head, general overview of Skid

Main bearing number 2 Crank shaft journal



Removed all right bank HT leads and coils, including spark plug extension,



Connecting rod journal 5



Connecting rod bearing 5R

turbos INSPECTION



cylinder head
checked

**left and right bank
carburetors to in-**



**Mounting release method was
carried out; as per Waukesha
1091 procedure as pictured be-
low I can confirm that release
method is complete and correct**



OUR TECHNICAL PARTNERS

OCS

Oil & Gas Systems Limited



www.southeycontracting.com



Euro Gas Systems



TOOLING LIST

COMPRESSOR TOOLING

Description
Enerpac P39 Steel Hand PumpsHydraulic Machinery Jacks / Enerpacks
Enerpac RSM-100 Pad Cylinder 10tonne Class 43 mm Closed Height 11,mm Stroke
Enerpac HC7206 Hose Assemblies 1.8 Meters Long
Feeler Gauge set
Allen Keys
RBK 3/4" 12 point socket set AF
Stahlwllw 1/4" adaptor 1/2" plug 1/4"
Stahlwllw adapters 3/8" to 1/2"
Stahlwllw adapters 3/4" to 1"
BRIT EXP 14 pc 1" skt set
BRIT EXP 9pc LNG HEX Key sleeve set
BRIT EXP Sleeve Set 9pc lng HEX Keys SP head
RBK steel feeler gauges kit IMP 20 x 12" x 1/2"
Norbar Torque Wrench Model 400 3/4DR
Alignment Tool
SPARK PLUG SOCKET/EXT
SPARK PLUG SOCKET
PULLER,SPARK PLUG EXTENSION
V-BELT TENSION TESTOR
THERMOMETER,PORTABLE,INFRARED
GAS COMPRESSION GAUGE
COMPRESSION TESTER ADAPTER
TIMING LIGHT
SLACK TUBE MANOMETER
CSA SP PLUG CARRIER TOOL
VALVE ADJUSTING WRENCH
COMPRESSOR,4 VALVE SPRING
PISTON PULLER
RING COMPRESSOR
PLIERS,PIST RING EXPAND 238MM

Electricians pliers and strippers



Screwdrivers set



Digital multimeter



754 Calibrateur de process à fonction de documentation -HART



700P Modules de pression différentielle



Fluke-700HTPK Hydraulic Test Kit

At our site office



ONE TEAM FOR GLENCORE E&P
CANADA 2014



**Ariel JGK/4 and Waukesha GSI 7044 on the skid before installation and precomision-
ning at Mangara, Chad**



Oil metering inspection for Electrical heat tracing ,insulation and cladding

LACT



THANK YOU
NKO'O Martin Luther
CEO